BOQ Clarificarions – 1

Item No.	Description	Unit	Qty.	Clarifications
7	**Storages - 750mm Ht**			
	Providing and placing Pre-laminate Particle Board storage with openable doors of 750mm(ht), made up of 18mm thick Pre-laminate particle board with PVC edge banding and locking arrangement. Storage body is made of 18mm thick pre laminated particle Board conforming to IS : 12823 Interior Grade, The back of the unit is made from 9mm Preliminate board. All the exposed edges are with 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding. The top, side and hinged shutters are sealed with 2mm thick PVC edge banding. The units are assembled by knock down fittings such as Minifix & Dowels. All the hardware and Hinges are from Hettich/Ebco. Storage has Brushed SS finish handles and lock . Prelam storage unit of 1200mm ht and 450mm depth			
7.1	600mm W x 450 mm D x 750mmH Nos 20	Nos	20	**Unit will be in "Nos."**
7.2	750mm W x 450 mm D x 750mmH	Nos	20	
7.3	900mm W x 450 mm D x 750mmH	Nos	40	
8	Office Storages - 2100mm Ht.600mm width			
	Providing and placing Preliminate Particle Board storage with openable doors of 2100mm (ht), made up of 18mm thick Preliminate particle board with PVC edge banding and locking arrangement. Storage body is made of 18mm thick pre laminated particle Board conforming to IS : 12823 Interior Grade, The back of the unit is made from 9mm Preliminate board. All the exposed edges are with 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding. The top, side and hinged shutters are sealed with 2mm thick PVC edge banding. The units are assembled by knock down fittings such as Minifix & Dowels. All the hardware and Hinges are from Hettich/Ebco. Storage has Brushed SS finish handles and lock. Prelam storage unit of 2100 mm ht and 450mm depth (SQFT) stackable full ht storage			
8.1	1200mm W x 600 mm D x 2100mmH	Sqft	100	**Unit to be read as "sq.ft." instead of "Nos."**
8.2	900mm W x 600 mm D x 2100mmH	Sqft	620	
8.3	750mm W x 600 mm D x 2100mmH	Sqft	375	
8.4	Any Width x 600 mm D x 2100mmH	Sqft	100	

21.2	Providing and fixng circular bench for high tech class room Made of 25mm thick MDF board and the length sideshall be post-formed in half round using post forming laminate of 0.5mm thick and the other two short sides shall be covered with PVC edge band of 1.5mm thick. Size:- 900x400mm Table Structure/Frame:- Complete structure shall be made of 25x25x1.2mm square section but the bottom pipe touching the ground shall be made of 50x25x1.5mm rectangular section. Frame shall be painted with enamel paint. Front Cover & Shelf:- Made of 18mm thick MDF board and all the sides shall be covered with PVC edge band of 1.5mm thick. Plastic bush/ Adjuster to be provided at the bottom of the frame. Providing and Supplying Student Dual Desk made in 25 x 25 x 1.2mm thick ERW pipe and Prelam MDF part (Desk, Seat, Back and Front Modesty) made in 18mm Prelam MDF. Shelf and Side made in 0.7mm CRCA Steel. Metal Parts with 40-60 Micron Powder Coating and All Laminate Parts to have 2mm PVC Edge Banding on Exposed Edges and 0.8mm on other edges. Bench with Levellers. Complete product as per attached drawing.	Nos	175	**Unit to be read as "Nos." instead of "sq.ft."**
Item no. 21.2 and 22 are separate items. To be quoted as per BOQ item descriptions.				
32	Matress			
32.1	providing and fixing Coir Mattress 4.5" thick complete in all respect 4" thick comprising of 3" ISI marked rubberised coir of Medium grade as per standards laid down by BIS (IS1891:1978) with 1" soft foam topping bonded. To be covered with good quality poly-cotton fabric with 10mm quilt with double stitching on margin /edge One side usable. And 3 years replacement guarantee			
a	35"x78" x4.5"	Nos	**102**	• **Length of the mattress shall be 72" or as per length of the bed.** • **The mattresses shall be of "Sleepwell" company as per Tender specifications** • **Though the basic**
b	72"x78"x4.5"	Nos	**36**	

				cost of mattress has been mentioned as Rs. 15,000/- to Rs. 17,000/- however payment to this item shall be made as per original invoice from the Sleepwell Company.
29	Multimedia Digital Podiums for Classroom			**Rate shall be all inclusive with gadgets and accessories.**
29.1	Technical Features: Large 22" interactive tablet monitor. Simplied notebook interface makes for easy device connection.Simple design and operation. Compatible with all operating systems. Edupen Pro interactive software included Item Code: Aha-Simpo	Nos	**1**	
43.3	stainless steel grills in Shelf :Providing and fixing a stainless steel grills of 10 gauge in shelf as per standard kitchen requirement all the sliding , holding , fixing arrangement is included in the rates.	Kg	**300**	**Item is in Kg. Shall be as per finalised design / drawing.**
	Interior Work			
8	Wooden Dado-Preliminate PVC Insulated panels cladding			
	Providing and fixing synwood Preliminate panel 3'-0" to 4'- 0" height, 18-20mm thickness, finished with moulding/ guide rails as per architectural drawings along the exterior walls, staircase etc including wooden skirting / treatment for existing skirting, finished in all respect.	Sqft	**6500**	**Unit of Item shall be sq.ft.**